


# PUBLIC PRIVATE PARTNERSHIPS IN UPPER PROCTOR CREEK

SESWA 2016 Birmingham, AL October 20, 2016



## Future Mims Park, GA Dome & World Congress Center






### Future Mims Park Area Topo w/Combined Sewers











## **Upper Proctor Creek Basin – Capacity Relief Program**






In order to sustain improvements downstream, work and projects must first occur in the "UPPER" reaches of the Proctor Creek Basin

## Upper Proctor Creek Basin - Capacity Relief Program









# Multi-Phase – Capacity Relief Project

#### **Objective**

- Provide capacity relief
- Reduce CSOs
- Improve water quality

#### **Project Description**

- 400-acre drainage basin
- Flood relief for up to the 100-year (1%) stormwater event





## A Multi-phase Capacity Relief Program

#### **Objective**

Address combined CSOs; provide capacity relief; improve water quality

#### Phase I

- Capacity Relief Pipeline Project first of at least 5 coordinated projects
- Foundation of a larger program of capacity relief
- Public/Private Partnership with new Mercedes-Benz Stadium developer

#### Phase 2

- Will capture runoff in Mims Park area and allow for a much larger water feature and park amenity than community first envisioned with the Park Pride Study
- Water feature design incorporates the Green and walkways desired in the current Mims Park planning (reviewed by various parks partners)



## A Multi-phase Capacity Relief Program

#### **Objective**


Address combined CSOs; provide capacity relief; improve water quality

#### Phase 3

- A combined 3-5 MG sewer vault, similar to the recently installed Turner Field media lot was considered if pond volume proved inadequate
- May still be required: Necessity and specific requirements for the vault will be determined during design for Phase 2
- If required, should be smaller, given the size of the Mims Park Pond



# Phase 2 Early Water Feature Concept - Mims Park





## A Multi-phase Capacity Relief Program

#### Phase 4

- A redirection of future runoff from developing "The Gulch" area
- Stormwater flows would be removed from the combined sewer.
- Furthering the goal of eliminating combined sewer overflows

#### Phase 5

- Source for re-introducing controlled stream flows into the original streambed
- Opportunity to restore aquatic life to the properties that adjoin the stream
- Environmental concerns- flushing contaminants & trash in old streambed

#### **The Overall Program**

- Envisions further cost-sharing opportunities for future developments or redevelopments to share in the cost/benefits (in/around new stadium)
- Will provide near-term opportunities for large landowners to redirect some stormwater into the new capacity relief pipe and pond system
- Will incorporate plans already underway for various GI projects planned
- Local streets impacted by installation of the piping systems will be rehabilitated and improved to incorporate further GI elements and improve instances of localized ponding during heavy rain events.



## Scope-of-Work, Costs and Timeline

#### Phase 1 – Mitchell and Northside Capacity Relief Piping

- Description: Design and install 60-inch pipe along Northside Drive/Dome and 36-inch pipe along Mitchell Street towards the Gulch
- Cost \$\$\$: \$ 10 M
- Project Time Line: Start Date: May 2015 End Date: Late 2016

#### Phase 2 – Vine City Capacity Relief Piping and Capacity Relief Storage Facility

- Description: Design and install 60-inch pipe from Northside Drive to Mims Park. Design and install the Mims Park Capacity Relief Storage Facility
- Cost \$\$\$: \$ 18 M (Design, Pipe Install, Capacity Relief Storage Facility install)
- Project Time Line: Start Date: May 2015 End Date: Late 2017

#### Phase 3 – 4 MG Storage Vault (based upon results of Phase 2 design)

- Description: Combined Sewer Relief Vault
- Cost \$\$\$: \$ 12 M
- Project Time Line: Start Date: June 2016 End Date: Late 2017



## Scope-of-Work, Costs and Timeline

#### Phase 4 – Capacity Relief Pipe Network for "The Gulch"


- Description: Design and install storm pipe and connect to Phase 1 capacity relief pipe network
- Cost \$\$\$: \$8 M ++
- Project Time Line: Start Date: Early 2018 End Date: Late 2020

# Phase 5 – Pump & Pipe – Environmental Costs/Concerns with Restoring Bank-full Stream Flow


- Description: Design/install of 72-inch pipe from Mims Park to Proctor Creek (assumed proximate to the North Avenue CSO facility)
- Cost \$\$\$: \$ 17 M
- Project Time Line: Start Date: Early 2019 End Date: Late 2020




# **Modified Approach**








# Pipelines Network Development





## Storm Sub-Basin Alternatives





# Multi-Phase – Capacity Relief Project

#### Phase A

•	18	325
•	24	492


- · 30 395
- 42 41148 615
- · 60 473

#### Phase B

- · 24 1260
- · 42 130
- · 54 123


#### <u>Ultimate</u>

- · 24 848
- · 30 1303
- · 36 730
- 42 710





## Ga Power Transmission Line Relocation





## Mims Park – Capacity Relief Project

#### **Project Status**

- Combined system analysis completed
- Pipe routing analysis completed
- Capacity relief concepts being finalized for CMAR procurement Dec 2016
- Ongoing coordination with Department of Parks and Recreation and Trust for Public Land- a private partner to construct the park
- Full park design moving forward and closer to completion- Separate construction (private procurement) to commence 3<sup>rd</sup> Qrt, 2017
- Next steps:
  - Procurement and Legislation
  - Permitting



## Mims Park with Atlanta's New Skyline 2017!





#### **Contact Information**

Raymond J. Wilke, PE, Env SP,CFM,F.ASCE Senior Watershed Director <a href="mailto:rwilke@atlantaga.gov">rwilke@atlantaga.gov</a> 404-546-3284

Brian J. Rainwater, PE, Env SP, CFM
Senior Watershed Manager
<a href="mailto:brainwater@atlantaga.gov">brainwater@atlantaga.gov</a>
404-546-1275

City of Atlanta
Department of Watershed Management
Strategic Asset Management Division

