


Stormwater BMP and Stream Restoration in a City Park



Jeff Herr P.E., D.WRE
Jill Stachura
770.673.3673
JHerr@BrwnCald.com



Project Location

- Camp Creek in Metro Atlanta
- 7 sq. mile drainage area at project site
- Within 100 yr FEMA floodplain
- City owned property
- Greenway/city park



Site Information – Pre-restoration

- 900 linear feet on City-owned parcels
- 30 feet wide channel with 8 to 12 feet vertical banks
- Railroad overpass just upstream
- Upstream sand source



Camp Creek Existing Condition

- Incised channel, no connection to floodplain (Rosgen F-5)
- Poor habitat
- Stream eroding into left bank and encroaching on park facilities
- Steep, vertical banks - safety hazard to park patrons
- Debris jams throughout



Pre-construction conditions

- Municipal complex (courts, police, etc.)
- On downtown square, high visibility
- Park has large greenspace, amphitheater, walking trails, playground, etc.
- Camp Creek fenced off from park
- Five pipe outfalls; direct stormwater discharges to creek from 30 developed acres, no treatment
- Flooding problems in park




Pre-construction Monitoring

- Water Quality Sampling
 - High bacteria, high TSS during storms, high nitrogen, low DO
- Habitat Assessment
 - Suboptimal
- Benthic macro-invertebrate assessment
 - Poor
- Geomorphic measurements
 - F-5, Incised, aggraded in places
 - Debris jams




Developed 2 Alternative Conceptual Designs

- Priority 3 Stream Restoration
- Stabilize banks in place
- Create floodplain benches and reconnect to floodplain where feasible
- Remove concrete debris
- Revegetate




Selected Alternative 2 – Priority 1 Stream Restoration



- Relocate stream into right floodplain
- Utilize old channel for bioretention treatment of 30 acres
- Remove invasives and revegetate


Project Benefits


- Improved access to floodplain
- Moved stream away from park facilities
- Enlarged park area and provides new amenity for patrons
- Combined several storm sewer outfalls
- Bioretention stormwater treatment (3 cascading cells, fieldstone outfall) for 30 acres
- Nature trail




Design & Construction - Stream

- C-5 Type Channel
- 975 linear feet
- 0.2% slope
- 2 stone cross vanes
- 5 stone J-hooks
- 2 log J-hooks
- 3 double stone J-hooks
- Toe wood/brush mattresses
- Bankfull width 22-26 ft.; Dmax 4 ft.
- Bankfull benches





Determined using Figure 6.2
 "M" - Data was not within the
 "Conditions" diagram.



Brown and Caldwell
 Environmental Engineers
 and Consultants
 2015 Peachtree Dunwoody Ave., NE
 Atlanta, Georgia 30328

| | |
|------------------|--------------------|
| DATE: 02/20/2018 | DESIGN: 01/15/2018 |
| BY: JAC | CHECKED: JAC |
| APP'D: JAC | DATE: 02/20/2018 |
| PROJECT: 1805 | |



| DATE | REV. | DESCRIPTION | BY | DATE |
|------------|------|------------------------|-----|------------|
| 02/20/2018 | 1 | ISSUE FOR CONSTRUCTION | JAC | 02/20/2018 |





SWINNETT COUNTY
 DEPARTMENT OF WATER RESOURCES
 SWINNETT COUNTY, GEORGIA

LILBURN
 WATER
 AND CAMP C

STORMWA
 PARTIAL

1 Determined using Figure 4-24 from the Georgia Stormwater Management Manual - Volume 2
 "NW" - Data was not able to be used in the "Design of Storm Water Lines Maximum 15-Minute Conditions" diagram.



Brown and Caldwell

Environmental Engineers and Consultants
 2015 Peachtree Dunwoody Ave., Suite 100
 Atlanta, Georgia 30328

| | |
|------------------------|------------------------|
| DATE: 08/14/2013 | DESIGNER: J. L. WILSON |
| BY: J. L. WILSON | CHECKED: J. L. WILSON |
| APPROVED: J. L. WILSON | DATE: 08/14/2013 |

| NO. | REVISION |
|-----|----------|
| | |
| | |
| | |
| | |



| DATE | REV. | DESCRIPTION | BY | DATE | APP. |
|------|------|-------------|----|------|------|
| | | | | | |
| | | | | | |
| | | | | | |



WINNETT COUNTY
 DEPARTMENT OF WATER RESOURCES
 WINNETT COUNTY, GEORGIA

L.I. BUR
 WATER
 AND CAMP C

STORMWATER
 PARTIAL

Construction

- 150 days – Substantial Completion (March – July 2012); \$725,000
- First built new channel, Camp Creek isolated from construction
- Removed plug and activated new channel
- Combined outfalls and built 3 cascading bioretention cells
- Plantings – three phases



Stream Construction

Cleared and flagged for new channel



Roughed in new channel



Stream Construction



Stream Construction

Log vane



Scour log and toe wood/brush mattress



During Construction – Installing Fieldstone Cross Vanes, Structures 1 and 2



Stream Construction

Stone J-hook



Completed Stone J-hook



Completed Project



New Channel

Old Channel,
Now Bioretention

Completed Project



Completed Project




Completed Project



Design & Construction – Bioretention BMP

- 5 outfalls – total drainage area – 30 acres
- Designed system of 3 cascading bioretention cells in old channel
- Underdrain system with valve (only to be used if needed)
- Engineered soil
- Outfall connection to stream
- Plantings



Bioretention BMP

Underdrain Installation



Installing Engineered Soil



Bioretention BMP

Engineered soil Installed in 1-ft lifts, water in, no compaction



Type 3 Rip-rap at outfalls



Bioretention BMP

Cobble and mulch installed



Sod and Irrigation System



Completed Bioretention BMP



Thank you!

